


New Underground Storage Tank Compliance Dates

We strongly suggest not to wait until the last minute to come into compliance.



May 30, 2017	July 1, 2017	Conduct in 2019 (due by Jan. 1, 2020)		July 1, 2020
Cannot "field repair" a spill basin with epoxy, caulk or adhesive materials alone	New USTs must be double-walled/interstitial monitoring	1 st Spill Bucket Test required	New linings must be UL1856 'listed'	Vapor Monitoring sunsets as a release detection method (without chemical marker)
SIR reports must be returned to O/O by the 10 th of the following month	Replaced piping must be double-walled/interstitial monitoring	1 st Overfill Prevention Equipment Test		Groundwater Monitoring sunsets as a release detection method
Notify prior to change of product to biofuel	Dispenser replacement requires sump install	1 st Walkthrough inspection		
New Installation notice now 14 days (not 30 days)	Spill, Overfill and Containment Sump Test required at install	1 st operability test of release detection equipment		